Procurement summary

Room: ≈ 94 1/2 in × ≈ 122 1/16 in · **Stock tile:** ≈ 23 5/8 in × ≈ 23 5/8 in
Grout: ≈ 1/16 in · Saw kerf: 0 in · Layout origin: Top left · Rotation: locked
24 installed pieces · 8 tiles per box · Reserve (%): 10% · Box price (USD): $12.50

Estimate	Opened	Reserve	Target	Boxes	Supplied	Box surplus	Total (USD)
Conservative	24	3	27	4	32	5	$50.00
Verified plan	21	3	24	3	24	0	$37.50

Before ordering, confirm actual tile size, tiles per box, dye lot and box price with the supplier. Spare tiles are whole stock held back, not saw waste. Box surplus is additional to that reserve.